



**MILBANK**<sup>®</sup>  
ENERGY AT WORK

## U3849-O-2/150



Catalog Number	U3849-O-2/150	Mounting	Pedestal
Marketing Product Description	4 Terminal Ringless Plain Top Lever Bypass 2-150 Ampere Main Breaker Single Pedestal Direct Bury	Enclosure	G90 Galvanized Steel with Powder Coat Finish
UPC	784572492301	Jaw Quantity	4 Terminal
Length (IN)	4.844	Bypass Type	Lever Bypass
Width (IN)	13	Number of Meter Positions	1 Position
Height (IN)	64	Equipment Ground	2 Barrel Ground Lug
Brand Name	Milbank	Hub Opening	Plain Top
Type	Ringless Meter Socket	Load Side Wire Range	1 AWG - 300 kcmil
Application	Meter Socket With Main	Number Of Receptacles	0
Standard	UL Listed;Type 3R		
Voltage Rating	Up to 240 Volts Alternating Current		
Amperage Rating	320 Continuous Ampere		
Phase	1 Phase		
Frequency Rating	60 Hertz		
Size	4.844L x 13W x 64H		
Number Of Cutouts	2		
Cutout Size	Two 150 Ampere Main Breakers		
Cable Entry	Underground		
Terminal	3/8 Inch Stud		
Insulation	Glass Polyester		

Please consult serving utility for their requirements prior to ordering or installing, as specifications and approvals vary by utility and may require local electrical inspector approval. All installations must be installed by a licensed electrician and must comply with all national and local codes, laws and regulations. Milbank reserves the right to make changes in specifications and features shown without notice or obligation.